



**ABRIDGED SCOPE OF WORK FOR
Live Oak Elementary School Drainage &
John McDonogh High School Waterproofing**

***DISCLAIMER: The following Abridged Scope of Work is for INFORMATIONAL purposes only and in no way supersedes the specifications provided in the Bidding Documents.
DO NOT PREPARE BIDS USING THE ABRIDGED SCOPE OF WORK.***

Scope of Work includes, but is not limited to, the following:

Live Oak Elementary School

- Excavate the soil from the planter area at the building.
- Repair Bricks as needed including tuck pointing of old mortar joints.
- Check moisture before applying waterproofing.
- Replace old drainage from the gutters on the building to the city connection in the street.
- Apply the waterproofing to the bricks when moisture is at optimal content.
- Replace soil back to the planter.

John McDonogh High School

- Excavate the soil from the planter area at the building.
- If old mastic is HOT (asbestos) remove ACM and repair the Bricks as needed including tuck pointing of old mortar joints.
- Check moisture before applying waterproofing.
- Apply the waterproofing to the bricks when moisture is at optimal content.
- Replace soil back to the planter.